

V1.0 June 2018

BREEAM UK New Construction 2018 scheme assessment timeline

The assessment timeline tables included in the summary page of each category in the UK New Construction 2018 scheme manual have been reproduced in this Guidance Note. The timeline has been produced to assist with optimising project sustainability performance. It outlines at which stage credits should be addressed and ideally when these should be considered by the design team, planner, contractors, owners, occupiers and other members of the project team to achieve the highest possible BREEAM rating at the minimum cost. It demonstrates that where BREEAM advice is taken on too late within the design and construction phases a number of BREEAM credits may not be achieved or only at additional cost or disruption.

| | | | Plan of Work | | | | | | | | |
|----------|--|---|-------------------------|--------------------------|------------------------------------|------------------------------------|--|--------------|------------------------------|--|--|
| | | Sub credits | Strategic Definition | Preparation and Brief | Concept Design | Developed Design | Technical Design | Construction | Handover and Close Out | | |
| Manageme | nt | | | | | | | | | | |
| | | Project delivery planning | | | | | | | | | |
| Man 01 | Project brief and design | Stakeholder consultation | | | | | | | | | |
| | | BREEAM Advisory Professional | | | Maximise project performance | Maximise project performance | | | | | |
| Man 02 | Life cycle cost and service life planning | Life cycle cost | | | Elemental LCC | | Component level LCC options appraisal | | | | |
| | | Capital cost reporting | | | | | | | | | |
| | | Environmental management | | | | | | | | | |
| Man 03 | Responsible construction | BREEAM Advisory Professional | | | | | | | | | |
| | practices | Responsible construction management | | | | | | | | | |
| | | Monitoring of construction site impacts | | | | | | | | | |

| Design/management influence |
|--|
| Design/client decision |
| Design/management changes at a high cost |
| No further changes can be made |
| RIBA stage stipulated within BREEAM criteria |





| | | Commissioning - testing schedule and responsibilities | | | | | |
|------------|---|---|--|--|--|--|--|
| Man 04 | Commissioning and handover | Handover | | | | Building user guides and training schedules prepared | Building user guides and training schedules prepared |
| Man 05 | Aftercare | | | | | | |
| Health and | Wellbeing | | | | | | |
| Hea 01 | Visual comfort | | | | | | |
| Hea 02 | Indoor air quality | | | Indoor air quality plan | | | |
| Hea 04 | Thermal comfort | | | | | | |
| Hea 05 | Acoustic performance | | | Acoustician appointment | | | |
| Hea 06 | Security | | | | | | |
| Hea 07 | Safe and healthy surroundings | | | | | | |
| Energy | | | | | | | |
| Ene 01 | Reduction of energy use and carbon emissions | | | | | | |
| Ene 02 | Energy monitoring | | | | | | |
| Ene 03 | External lighting | | | | | | |
| Ene 04 | Low carbon design | Passive design | | Passive design analysis | | | |
| LHE 04 | Low Calbon design | Low and zero carbon technologies | | Feasibility study | | | |
| Ene 05 | Energy efficient cold storage | Refrigeration energy consumption | | Strategy for design and Installation | | | |
| Ene 06 | Energy efficient transportation systems | | | | | | |

| Design/management influence | | | | | |
|--|--|--|--|--|--|
| Design/client decision | | | | | |
| Design/management changes at a high cost | | | | | |
| No further changes can be made | | | | | |
| RIBA stage stipulated within BREEAM criteria | | | | | |





| Ene 07 | Energy efficient laboratory systems | Design specification | | Client engagement | | | | |
|-----------|--|---------------------------------|---|--|--|-------------------------|--|--|
| Ene 08 | Energy efficient equipment | | | | | | | |
| Transport | | | | | | | | |
| Tra 01 | Transport assessment and travel plan | | Travel plan | | | | | |
| Tra 02 | Sustainable transport measures | | Consultation with local authority (option 6 only) | | | | | |
| Water | | | | | | | | |
| Wat 01 | Water consumption | | | | | | | |
| Wat 02 | Water monitoring | | | | | | | |
| Wat 03 | Water leak detection | | | | | | | |
| Wat 04 | Water efficient equipment | | | | | | | |
| Materials | | | | | | | | |
| Mat 01 | Environmental impacts from construction products - Building life cycle assessment | | | Building LCA submission | | Building LCA submission | | |
| Mat 02 | Environmental impacts from construction products | | | | | | Installation of certified products | |
| Mat 03 | Responsible sourcing of materials | Sustainable procurement plan | Sustainable procurement plan | Review sustainable procurement plan | Review sustainable procurement plan | | | |
| Mat 05 | Designing for durability and resilience | | | | | | | |
| Mat 06 | Material efficiency | | Stage actions | Stage actions | Stage actions | Stage actions | Stage actions | |

| Design/management influence | | | | | |
|--|--|--|--|--|--|
| Design/client decision | | | | | |
| Design/management changes at a high cost | | | | | |
| No further changes can be made | | | | | |
| RIBA stage stipulated within BREEAM criteria | | | | | |





| | | | | | , | |
|-------------|--|--|--|--|---|---|
| Waste | 1 | | | | | |
| Wst 01 | Construction waste management | | | Pre- demolition audit | | |
| Wst 02 | Use of recycled and sustainably sourced aggregates | | | | | |
| Wst 03 | Operational waste | | | | | |
| Wst 04 | Speculative finishes | | | | | |
| Wst 05 | Adaptation to climate change | | | Climate adaptation strategy appraisal | | Update on climate adaptation strategy appraisal |
| Wst 06 | Design for disassembly and | Design for disassembly and functional adaptability | | Disassembly and functional adaptation study | | |
| | adaptability | Disassembly and functional adaptability – implementation | | | | |
| Land Use an | d Ecology | | | | | |
| LE 01 | Site selection | Previously occupied land | | | | |
| LL UI | Site Selection | Contaminated land | | | | |
| LE 02 | Identifying and understanding the risks and | Survey and evaluation | | | | |
| LE UZ | opportunities for the site | Determining the site wide outcomes | | | | |
| LE 03 | Managing negative impacts on ecology | | | | | |
| LE 04 | Enhancing site ecology | | | | | |
| LE 05 | Long term ecology management and maintenance | | | | | |

| Design/management influence |
|--|
| Design/client decision |
| Design/management changes at a high cost |
| No further changes can be made |
| RIBA stage stipulated within BREEAM criteria |



GN37 1.0 PN344 © BRE Global Ltd, June 2018



Guidance Note GN37

| Pollution | Pollution | | | | | | | |
|-----------|---|--|--|--|--|--|--|--|
| Pol 01 | Impact of refrigerants | | | | | | | |
| Pol 02 | Local air quality | | | | | | | |
| Pol 03 | Flood and surface water management | | | | | | | |
| Pol 04 | Reduction of night time light pollution | | | | | | | |
| Pol 05 | Reduction of noise pollution | | | | | | | |

| Design/management influence |
|--|
| Design/client decision |
| Design/management changes at a high cost |
| No further changes can be made |
| RIBA stage stipulated within BREEAM criteria |

